



TETA

IT,AIRCON & NETWORKING

Specification Sheet

Nuwave Industries cc t/a
Nuwave Business Furniture
Millennium Business Park
Unit 175,Block F
Edison Way, Century City
Tel: 021 418 4933

AREA	ITEM	DESCRIPTION	PICTURE	QTY
Open Office & Closed	Power Cables			
		PL-4 Way Dual 2C,1N+ Germ	NA	10
		PL-Input cable 6m grey SA Clean	NA	1
		PL-Input cable 6m black SA Normal	NA	1
		PL-Input cable 3m grey SA Clean	NA	6
		PL-Input cable 3m black SA Normal	NA	6
		PL-Intercon cable 3m grey SA Clean	NA	3
		PL-Input cable 3m black SA Normal	NA	3
Open Office	Air Conditioner			
		24000 BTU Unit Either wall mounted (if wall mounted, a pump must be included), or ceiling mounted cassette unit (suspended ceiling needs minimum of 400mm void for cassette unit)		1
Open Office	Networking			
		Install - Cat6 network point including fly and patch leads		
Office 1	Air Conditioner			
		Remove existing unit (if there is) and replace with new 12000 BTU Unit		1
Office 1	Networking			
		Install - Cat6 network point including fly and patch leads		
Meeting Room	Air Conditioner			
		Remove existing unit (if there is) and replace with new 12000 BTU Unit		1
Meeting Room	Networking			
		Install - Cat6 network point including fly and patch leads		1
Office 2	Air Conditioner			
		Remove existing unit (if there is) and replace with ne 12000 BTU Unit		1
Office 2	Networking			
		Install - Cat6 network point including fly and patch leads		
Office 3	Air Conditioner			
		Remove existing unit (if there is) and replace with ne 12000 BTU Unit		1
Office 3	Networking			

		Install - Cat6 network point including fly and patch leads		
Office 4	Air Conditioner			
		Remove existing unit (if there is) and replace with ne 12000 BPU Unit		1
Office 4	Networking			
		Install - Cat6 network point including fly and patch leads		
Office 5	Air Conditioner			
		Remove existing unit (if there is) and replace with ne 12000 BTU Unit		1
Office 5	Networking			
		Install - Cat6 network point including fly and patch leads		1
Office 6	Air Conditioner			
		Remove existing unit (if there is) and replace with ne 12000 BPU Unit		1
Office 6	Networking			
		Install - Cat6 network point including fly and patch leads		
Server Room				
		As per clients specifications		1
Server Room	Air Conditioner			
		Remove existing unit (if there is) and replace with ne 12000 BTU Unit (either console or wall mounted depending on whether wall has prepared space. This is over spec-ed, yet due to the valuable nature of the equipment, it's the better option.)		1
Boardroom	Power Docks in Desk			
		PL-Rotadock Silver 2 end caps, 1 reset swich, 2 normal 3-pin sockets, 1 Schuko 2-pin socket, 2 spacers 12.5mm, 2 COMMS Modules: 1) VGA & Audio plate + leads; and 2) HDMI & data plate + couplers only & 1 bypass connector		2
Training Rooms	Networking			
	On on each side	Install - Cat6 network point including fly and patch leads		2